Item No	Description
10	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machinemixed, concrete laid in layers not exceeding 15 cms, thick well compacted in foundation and plinth, cost of all materials, labour HOM of machinery, curing complete as per specifications.
11	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks,& Plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications Footing
12	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks,& Plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications Columns
13	Providing & removing centering shuttering, strutting, propping etc., and removal of form work for foundations, footings bases of columns for mass concrete including cost of all materials, labour complete as per specifications Footing
14	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.
15	Providing and laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25 Plinth Beam
16	Providing and laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25 Roof Slab

unit	Previous		Present Measurement			Total Up-today	
	Qty	Cost			Cost	Qty	Cost
CUM	0.00	0.00	134.35	6000.00	806100.00	134.35	806100.00
CUM	0.00	0.00	78.84	7300.00	575532.00	78.84	575532.00
CUM	0.00	0.00	19.74	7300.00	144102.00	19.74	144102.00
SQM	0.00	0.00	196.56	300.00	58968.00	196.56	58968.00
SQM	0.00	0.00	169.76	500.00	84881.00	169.76	84881.00
CUM	0.00	0.00	29.21	7300.00	213252.00	29.21	213252.00
CUM	0.00	0.00	87.89	7300.00	641583.00	87.89	641583.00